
# CITY OF SALEM, MA ROSIES POND & JEFFERSON AVENUE FLOOD MITIGATION PROJECT

ISSUED FOR BID
CONTRACT NO. T-47
JUNE 2018





PROJECT LOCATION MAP


DRAWING INDEX				
Sheet Number	Sheet Title	Sheet Description		
1	G-000	TITLE SHEETS		
2	G-001	GENERAL NOTES, LEGEND, ABBREVIATIONS & PROJECT INDEX PLA		
3	C-100	EXISTING CONDITIONS & SITE PREPARATION PLAN - 1		
4	C-101	EXISTING CONDITIONS & SITE PREPARATION PLAN - 2		
5	C-102	EXISTING CONDITIONS & SITE PREPARATION PLAN - 3		
6	C-200	SITE PLAN - 1		
7	C-201	SITE PLAN - 2		
8	C-202	SITE PLAN - 3		
9	C-300	SHEET PILE RETAINING WALL ALIGNMENTS		
10	C-301	SHEET PIPE RETAINING WALL ALIGNMENTS		
11	C-302	SHEET PILE RETAINING WALL PROFILES		
12	C-303	SHEET PILE RETAINING WALL PROFILES		
13	C-304	SHEET PILE RETAINING WALL PROFILES		
14	C-305	SHEET PILE RETAINING WALL PROFILES		
15	D-400	DETAILS - 1		
16	D-401	DETAILS - 2		
17	D-402	DETAILS - 3		
18	D-403	DETAILS - 4		
19	E-500	EASEMENT PLAN 1		
20	E-501	EASEMENT PLAN 2		
21	S-001	STRUCTURAL NOTES, ABBREVIATIONS, REPAIR NOTES & SCHEDUL		
22	S-002	LAWRENCE STREET HEADWALL PLAN, DETAILS, & SECTIONS		
23	S-003	JEFFERSON AVENUE CHANNEL PLAN & DETAILS		




40 Shattuck Road, Suite 110 Andover, Massachusetts 01810 866.702.6371 | www.woodardcurran.com

**COMMITMENT & INTEGRITY DRIVE RESULTS** 

WC PROJECT NO. 224405.01







# **ABBREVIATIONS**

& A.G.	AND ABOVE GROUND
B BIT. BM BVW	BORING BITUMINOUS BENCHMARK BORDERING VEGETATED WETLAND
CB CMP COMM CONC COND.	CATCH BASIN CORRUGATED METAL PIPE COMMUNICATION CONCRETE CONDUIT
DI DIA. DMH DS	DUCTILE IRON DIAMETER DRAIN MANHOLE DOWN—SPOUT
E EL. EMBED. EX.	UNDERGROUND ELECTRICAL ELEVATION EMBEDDMENT EXISTING
FF FIN. FL. FT	FINISH FLOOR FINISH FLOOR FOOT/FEET
GALV. GRAN.	GALVANIZED GRANITE
HDPE HWY HYD	HIGH DENSITY POLYETHYLENE HIGHWAY HYDRANT
IN INV. IVW	INCH INVERT INLAND VEGETATED WETLAND

INLAND VEGETATED WEILAND

LIGHT POST LINEAR FEET LAND UNDER WATER MAHW MEAN ANNUAL HIGH WATER MAX.


MAXIMUM MINIMUM MON MONUMENT NBVW NON-BORDERING VEGETATED

NO REFUSAL N.T.S. NOT TO SCALE

WETLAND MAX. NUMBER OUTSIDE DIAMETER OVERHEAD ELECTRIC OVERHEAD PLUS OR MINUS PROFESSIONAL LAND SURVEYOR PLS PVC POLYVINYL CHLORIDE R.O.W. RIGHT-OF-WAY REINFORCED CONCRETE PIPE RCP REINF. REINFORCED REQ'D REQUIRED RET RETAINING REGISTERED LAND SURVEYOR RTE ROUTE SLOPE SEWER STORM DRAIN SEWER MANHOLE SCH SCHEDULE STANDARD DIMENSION RATIO STA. STATION T.O.W. TOP OF WALL UNDERGROUND CABLE UNLESS NOTED OTHERWISE U.N.O. WITH WATER VALVE WELDED WIRE MESH

S , LEGEND, JECT INDE)

IOB NO.: 224405.01 ATF: JUNE 2018 SCALE: AS NOTED SHEET: 2 OF 23



16. RESTRICT ACCESS TO SITE THROUGH THE USE OF APPROPRIATE SIGNAGE, BARRIERS, 17. CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL NECESSARY CONSTRUCTION 18. ALL WORK ASSOCIATED WITH THE PROJECT SHALL BE COMPLETED IN ACCORDANCE

FENCES, FTC. SITE SHALL BE LEFT WITH APPROPRIATE SAFETY MEASURES IN PLAC

DURING BOTH WORKING AND NON-WORKING HOURS.

ADEQUATE TIME SO AS NOT TO DELAY CONSTRUCTION.

DOT STANDARD SPECIFICATIONS.

PAYMENT OF FINAL RETAINAGE.

DURING NON-WORKING HOURS. SITE SAFETY IS THE RESPONSIBILITY OF CONTRACTOR,

PERMITS. PERMIT APPLICATIONS, INCLUDING "PERMIT TO OPEN OR OCCUPY STREET/ SIDEWALK" FROM THE CITY. PERMIT APPLICATIONS SHALL BE SUBMITTED WITH

WITH THE CITY OF SALEM BYLAW AND LOCAL REGULATIONS AND MASSACHUSETTS

THAT REFLECT ANY AND ALL MODIFICATIONS TO THE FLOOD MITIGATION SYSTEM AND

SUBMITTED TO THE CITY ENGINEER. THESE DRAWINGS SHALL BE SUBMITTED IN BOTH

ANY OTHER UTILITY INSTALLATIONS OR ALTERATIONS WITHIN THE PROJECT LIMITS BE

DIGITAL AND HARD COPY FORMAT AS DEFINED IN THE SPECIFICATIONS PRIOR TO

19. UPON COMPLETION OF CONSTRUCTION, A COMPLETE SET OF "RECORD" DRAWINGS

20. WORK IS IN CLOSE PROXIMITY TO EXISTING UTILITIES. PROTECTION OF EXISTING UTILITIES DURING CONSTRUCTION SHALL BE PROVIDED AT NO ADDITIONAL COST. 21. ALL DEWATERING ACTIVITIES SHALL MEET LOCAL, STATE, AND FEDERAL REGULATIONS.

22. THE CONTRACTOR IS RESPONSIBLE FOR ALL LABOR AND EQUIPMENT REQUIRED TO PERFORM THE WORK INCLUDING BUT NOT LIMITED TO PROPER SHORING, DEWATERING

23. PROPERTY AND RIGHT OF WAY LOCATIONS SHOWN ARE APPROXIMATE AND DO NOT REPRESENT A PROPERTY SURVEY. PROPERTY BOUNDARIES BASED UPON ASSESSOR PLANS ON FILE WITH SALEM, MASSACHUSETTS GIS DEPARTMENT. A BOUNDARY SURVEY WILL BE COMPLETED AND EASEMENTS FOR ENCROACHMENTS ONTO PRIVATE PROPERTIES WILL BE EXECUTED PRIOR TO CONSTRUCTION. NO WORK SHALL BE

24. ALL DISTURBANCE TO THE SITE SHALL BE WITHIN THE DEFINED LIMIT OF WORK. IF A CONFLICT OR SITE CONDITION REQUIRES THAT THE LIMIT OF WORK BE CHANGED,


PERFORMED UNTIL ALL REQUIRED EASEMENTS ARE OBTAINED.


CONTRACTOR SHALL COORDINATE WITH THE ENGINEER.


EQUIPMENT, AND WATER TREATMENT EQUIPMENT IN ACCORDANCE WITH THE SPECIFICATIONS AND ALL LOCAL, STATE, AND FEDERAL REGULATIONS.


G-001


CHECK GRAPHIC SCALE BEFORE USING
































Temporary Ero	osion Control	
Measure	Dates For Use	Timing, Activity, and Location
Sedimentation Barrier	ALL	Before soil disturbance, install downhill of areas to be disturbed and around material stockpiles.
Up-slope Diversion	ALL	Before soil disturbance, install uphill of areas to be disturbed and material stockpiles.
Catch Basin Protection	ALL	Before soil or pavement disturbance, install ACF Environmental, Inc. High Flow Siltsack, Siltsaver Inlet Filter. or equal, installed per manufacturer's requirements.
Dust Control	ALL	During dry weather, apply water and calcium chloride to control dust.
Temporary Seeding	April 15 to Oct. 15	Soil stockpiles that are not covered and disturbed areas that will not be disturbed again within 14 days. If grass growth provides less than 95% soil coverage by Nov. 1, apply mulch and anchor with erosion control blanket.
Mulch	April 15 to Sept. 15	On all areas of exposed soil prior to rain events apply 100—150 lbs (2.5 bales) per 1,000 sq ft. by mechanical blower.
Winter Mulch	Sept. 16 to Oct. 31	On all areas of exposed soil prior to precipitation apply 150 to 170 lbs. mulch (4 bales) per 1,000 sq. ft. by mechanical blower. Erosion control blanket may be used as a substitute for winter mulch.
	Nov. 1 to April 14	On all areas of exposed soil, apply 150 to 170 lbs. mulch (4 bales) per 1,000 sq. ft. and anchor with netting <u>at the end of each working day.</u> Erosion control blanket may be used as a substitute for winter mulch.
Inspections	Until site is permanently stabilized	Inspect the erosion and sedimentation control measures daily, and maintain and repair as necessary.

### Permanent Erosion Control:

Measure	Dates For Use	Timing, Activity, and Location
Pavement — Base Course — Final Course		Install only in areas shown on the plan, shortly after pavement base is brought to final grade. Install near completion of project.
Permanent Seeding	April 15 to Sept. 15	On final grade areas, within 7 days of grade preparation, prepare topsoil, followed by seed and mulch application.
Dormant Seeding	Sept. 16 to April 15	On final grade areas, with prepared topsoil. Apply seed at double the specified rate on bare soil, and follow with an application of winter mulch.
Ground Cover, Trees, Shrubs	April 15 to Nov. 1	Install with final landscaping.
Permanent Mulch	ALL	Install with final landscaping.
Turf Reinforcement Mat (TRM)	ALL	Install with final landscaping.

#### Inspections:


Regular inspections of all erosion and sedimentation controls shall be made at least weekly and prior to and following storm events. Minimum inspections shall be made as listed in the table below.

The state of the s			
Inspected Item	Look For		
Mulched Surfaces	Thin mulch or inadequate application. Wind movement.		
Seeded Surfaces	Poor seed germination. Loss of mulch. Development of rivulets.		
Sediment Barrier	Sediment build—up to one half the height of the barrier. Undermining of the barrier. Supporting stakes loose, toppled, or unmarked. Breaks in barrier.		
Perimeter Diversion	Discharge is to stabilized area. Erosion or breaks in barrier. Supporting stakes loose, toppled or unmarked.		
Catch Basin Protection	Sediment build—up and structure blockages. Slow flow/Ponding water. Breaks in fabric or voids in barrier.		
Dewatering Filter	Breaks in fabric or supporting structure. Slow flow, indicating high sediment build—up.		
Construction Entrance	Sedimentation of roadways. Off—site dust complaints.		

#### ROPE TO ANCHOR IN-PLACE BOOM - 4" PVC PIPE WITH CAPPED ENDS, OR STYROFOAM AS RECOMMENDED BY MANUFACTURER GEOTEXTILE FABRIC WITH DOUBLE STITCHED SEWN POCKET AT TOP AND 1' ABOVE BOTTOM MIRAFI 1160N OR APPROVED EQUAL NON-CORROSIVE CHAIN OR CABLE BALLAST TO SECURE BOTTOM OF CURTAIN, MIN. 1LB/FT 1' MIN. SKIRT BELOW BALLAST NON-CORROSIVE ANCHOR AT EACH END AND AT INTERMEDIATE LOCATIONS AS WARRANTED


- 1. MAINTENANCE: INSPECT FOR BREAKS IN FABRIC, MISSING OR INADEQUATE BOOM, BALLAST, OR ANCHORS.
- 2. REMOVAL: THE COMPLETE INSTALLATION SHALL BE REMOVED NO SOONER THAN 24 HOURS AFTER DISTURBANCE HAS CEASED.
- 3. SKIRT SHALL CONFORM TO IRREGULAR SHAPED CHANNEL BOTTOM AS NECESSARY.


# TURBIDITY CURTAIN



SECTION

PLAN VIEW <u>SEDIMENT BARRIER - SILTSOXX</u>






**PROFILE** 


- CONSTRUCTION ENTRANCES MAY BE RELOCATED AS CONSTRUCTION PROGRESSES.
- WHEEL WASH PITS MAY ALSO BE USED, IF APPROVED. MAINTENANCE: INSPECT FOR EFFECTIVE REMOVAL OF SOIL FROM VEHICLES PRIOR TO LEAVING THE SITE. SWEEP ANY SOIL FROM ADJACENT ROADWAYS.

REMOVAL: AT LEAST ONE CONSTRUCTION ENTRANCE THE SITE ARE STABILIZED.

## STABILIZED CONSTRUCTION ENTRANCE DETAIL



PUMPED DISCHARGE SEDIMENT CONTROL DEVICE





- INSTALL FABRIC ON UPHILL SIDE OF SUPPORT POSTS
- INSTALL SILT FENCE ACROSS SLOPES
- SILT FENCE SHALL NOT BE USED IN DRAINAGE WAYS

MAINTENANCE: INSPECT FOR TEARS IN THE FABRIC OR DAMAGE TO SUPPORTS. REPAIR AS NECESSARY. REMOVE ACCUMULATED SEDIMENT WHEN IT REACHES A DEPTH OF SIX-INCHES OR LESS.

WHEN UPSLOPE AREAS ARE STABILIZED, THE STRUCTURE AND ANY ACCUMULATED SEDIMENT WILL BE REMOVED. REMOVAL:


# SEDIEMENT BARRIER - SILTATION FENCE






COFFERDAM DETAIL SHOWN FOR REFERENCE PURPOSES. CONTRACTOR SHALL PROVIDE DESIGN OF TEMPORARY COFFERDAMS, STAMPED BY A LICENSED PROFESSIONAL ENGINEER IN THE STATE OF MASSACHUSETTS.

# TEMPORARY FRAME & FABRIC COFFERDAM DETAIL




SEDIMENT BARRIER - HAYBALE BARRIER



# ROLLED EROSION CONTROL BLANKET

#### **ROLLED EROSION CONTROL BLANKET NOTES:**

- PREPARE SOIL BEFORE INSTALLING ROLLED EROSION CONTROL PRODUCTS (RECP's), INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED AS WELL AS REMOVING ANY PROTRUDING ROCKS, STUMPS OR ROOTS. DURING THE GROWING SEASON (APRIL 15-SEPTEMBER 15) USE RECP'S ON THE BASE OF GRASSED WATERWAYS, SOIL SLOPES HAVING A GRADE GREATER THAT 15%, OR ANYWHERE WHERE HAY MULCH HAS PROVEN TO BE INEFFECTIVE AT CONTROLLING SHEET EROSION. RECP'S ARE A MANUFACTURED COMBINATION OF MULCH AND NETTING DESIGNED TO PREVENT EROSION AND RETAIN SOIL MOISTURE.
- 2. FOR OVER WINTER PROTECTION, APPLY RECP'S ON THE BASE AND SIDE SLOPES OF GRASSED WATERWAYS AND ON SLOPES STEEPER THAN AN 8% GRADE.
- 3. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE RECP'S IN A 6" DEEP X 6" WIDE TRENCH WITH APPROXIMATELY 12" OF RECP'S EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE RECP'S WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" PORTION OF RECP's BACK OVER SEED AND COMPACTED SOIL. SECURE RECP'S OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" APART ACROSS THE WIDTH OF THE
- 4. ROLL THE RECP's (A.) DOWN OR (B.) HORIZONTALLY ACROSS THE SLOPE. RECP's WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL RECP'S MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE. WHEN USING THE DOT SYSTEM, STAPLES/STAKES SHOULD BE PLACED THROUGH EACH OF THE COLORED DOTS CORRESPONDING TO THE APPROPRIATE STAPLE PATTERN.
- 5. THE EDGES OF PARALLEL RECP's MUST BE STAPLED WITH APPROXIMATELY 2" 5" OVERLAP DEPENDING ON RECP's TYPE.
- 6. CONSECUTIVE RECP'S SPLICED DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STYLE) WITH AN APPROXIMATE 3" OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" APART ACROSS ENTIRE RECP's WIDTH. NOTE: \*IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" MAY BE NECESSARY TO PROPERLY SECURE THE RECP's.
- 7. UNTIL GRASS IS ABUNDANT, INSPECT PERIODICALLY AND AFTER EACH RAINSTORM TO CHECK FOR EROSION. IMMEDIATELY REPAIR AND ADD MORE MULCH UNTIL GRASSES ARE FIRMLY
- 8. DO NOT MOW THE FIRST YEAR.
- 9. DETAIL SHALL BE CONSIDERED GENERAL GUIDANCE FOR RECP INSTALLATION; CONTRACTOR SHALL INSTALL RECP IN ACCORDANCE WITH MANUFACTURER RECOMMENDATIONS.



IOB NO.: 224405.01 ATE: JUNE 2018 SCALE: AS NOTED SHEET: 15 OF 23

D-400

