

**ADDENDUM #1**  
**INVITATION FOR BIDS R-32**  
**WINTER ISLAND SCENIC TRAIL**  
**OCTOBER 23, 2015**

**1. On plan L-001 there is a designation "Remove and Stock Pile Utility Poles", but no poles are shown on the plan nor is there a quantity designated. How many poles are expected to be removed, and of what size?**

The exact number is unknown, due to the amount of overgrown vegetation in that area, but it's reasonable to expect (20) 10 ft. segments of standard wood utility pole.

**2. On detail sheet L-005, detail 6 calls for a stone retaining wall made of granite block to be placed alongside an area of chip seal path. No wall is shown on the plan and all measurements on this detail say "Varies". What size and length of wall are you looking for, and in what portions of the chip seal surface path is this wall to be placed?**

The granite retaining walls were removed from the specifications. That detail should have been removed as well. Please disregard.

**3. On Page L-007 the details for the stormwater bioinfiltration system in add alternate 1 don't show what materials are to be used in the plumbing of the system (PVC, Ductile Iron, Cast Iron, Schedule 40, etc.)?**

All piping is high density polyethylene.

**4. What material is the bioinfiltration system made of?**

The vault is precast concrete.

**5. What materials are the pre-filter cartridges made of?**

Filter netting is 100% polyester with a number 16 sieve size.

**6. Do you have a certain brand in mind?**

The basis of design is Modular Wetland Systems, Inc or equals.

**7. Also, are the manholes to be domestic or foreign make?**

Manholes can be domestic or foreign.

**8. Will this system connect to an existing drain line? If so where is this line located, as none is shown on plan L-002.1 but an outlet pipe is shown on L-007?**

The system does not connect to an existing drain line, it is stand alone.

**9. Please identify the time for performance?**

The performance period is identified in the Invitation for Bids. The work is expected to begin in November and must be complete by June 30, 2016.

**10. Please provide loam test results.**

No loam test results are available for the existing topsoil.