

**ADDENDUM #1**  
**CITY OF SALEM IFB 23-49-PLAN: GALLOWS HILL PARK FIELD REPAIRS**  
**APRIL 13, 2023**

**Timing of Alternative #1**

Aerating, overseeding and fertilizing to be done in the Fall 2023, not spring 2024

**Locations and extents of baseball field repair**

AutoCAD file will be provided to contractor for contractor to layout locations and extents. City to review and confirm with the contractor.

**Mowing**

Contractor is responsible for areas seeded as part of this work per the maintenance requirements outlined in specification section 32 92 00 Turf and Grasses. City will mow the lawn areas not seeded by the contractor.

**Water**

The irrigation system will be turned on and water is available for contractor use. Irrigation timing can be adjusted for seed establishment.

**Area drain in left center field noted to be raised (L-1 #29 Raise Area Drain)**

Contractor to carry cost to raise or lower the rim. Elevation to be confirmed during construction.

**Remove boulder in outfield (L-1 left center field):**

Per the Earth Moving specification any stone up to 3 cubic yards is considered unclassified excavation. Should the stone to be removed be larger than 3 cubic yards the City will advise how to proceed.

**Existing 24" Nyloplast Area Drain in southern rain garden**

Contractor to connect 6" HDPE perforated pipe to Nyloplast area drain at existing invert and install cap or plug in the interior of the structure.

All other terms and conditions apply.